



Case History LANDFILL CLOSURE IMPLEMENTATION

**SPERLING
HANSEN
ASSOCIATES**

North Ravine Closure, Campbell Mountain Landfill.

- *SHA designed final closure for North Ravine using local lake edge silts (1000 mm) and biosolids compost produced at the landfill (300 mm).*
- *Closure was completed over 0.7 Ha area over 3 months in 1998.*
- *Construction involved delivery of clay, compaction to 95% Proctor and construction of shot-crete seals on edges of ravine to minimize air entry.*
- *Total cost of closure was \$245,000 involving \$110,000 for construction, \$95,000 for materials, \$20,000 for roads & \$25,000 for run-off ditching.*
- *SHA provided design, QA/QC and project management.*

*RDOS Contact: Ernie Obst (250) 490-4142
Project Budget \$ 40,000.*



SPERLING HANSEN ASSOCIATES

**#8-1225 East Keith Road, North Vancouver, B.C.
Phone (604) 986-7723 Fax (604) 986-7734
E-Mail: sperling@sperlinghansen.com**

- *Landfill Siting*
- *Landfill Closure*
- *Hydrogeological Investigation*
- *Environmental Monitoring*
- *Design and Operations Plans*